

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT18523/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Improvements to Roads and Drains at Singapura Village Surrounding Areas in Ward No. 11 (Kavempunagara), Vidyaranyapura Sub Division.


Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				JAYAPRAKASH T		
				In Figures		In Words
1	227.22	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	75.0	17041.50	Rupees Seventy Five Only
2	214.44	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4579.0	981920.76	Rupees Four Thousand Five Hundred Seventy Nine Only
3	6.48	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4430.0	28706.40	Rupees Four Thousand Four Hundred Thirty Only
4	10.8	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications etc complete as per specifications and directions of engineer in charge of the work	Sqm	80.0	864.00	Rupees Eighty Only
5	1.08	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4958.0	5354.64	Rupees Four Thousand Nine Hundred Fifty Eight Only
6	7.19	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	277.0	1991.63	Rupees Two Hundred Seventy Seven Only
7	179.83	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams etc complete as per specifications and directions of engineer in charge of the work	Cum	5718.0	1028267.94	Rupees Five Thousand Seven Hundred Eighteen Only

[Signature]

[Signature]
30/3/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of		
				JAYAPRAKASH T		
				In Figures		In Words
8	0.22	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	63035.0	13867.70	Rupees Sixty Three Thousand Thirty Five Only
9	1418.8	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratory, Power Floater, blade and disc etc complete as per specifications and directions of engineer in charge of the work	Sqm	80.0	113504.00	Rupees Eighty Only
10	135.3	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator and HOM of machinery including cost of blade coolant etc including cleaning of groove and providing sand and hot bitumne fillars, and filler metal etc., including cost of conveyance of all materials, labours, lead and lift charges and all other incidental charges as per drawing and as per specification Concrete Pavement etc complete as per specifications and directions of engineer in charge of the work	Rmt	105.0	14206.50	Rupees One Hundred Five Only
11	170.42	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 11.90 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	195.92	33388.69	Rupees One Hundred Ninety Five and Ninety Two Paise Only
					2239113.76	


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
30/03